of the Patel of Joldhal. Persons having any right to the teak poles are requested to submit a statement of their claims in writing to the District Forest Officer, Bhadravati Division within one month from the date of publication of this notice, failing which the teak pieces will lapse to Government under section 42 of the said Regulation.

No.		Length.		Girth.		C.ft.
1.	Teak	12—0	x	3—0	=	6—9
2.	,,	10—0	x	3—0	=	5—7
3.	,,	14—6	x	2—3	=	4—6
4.	,,	10—0	x	1—8	=	1—8
5.	,,	10—0	x	—0	=	2—6
6.	,,	14—6	x	1—9	=	2—9
7.	Teak	15—6	x	1—8	=	2—8
8.	,,	15—6	x	1—8	=	2—8
9.	,,	14—9	x	1—3	=	2—9
10.	,,	13—6	x	2—0	=	3—4
11.	,,	5—0	x	2—4	=	1—8
12.	,,	9—0	x	1—9	=	1—8

Notification dated 8th January 1932.

Notice is hereby given under Section 40 of the Mysore Forest Regulation that the following teak trough and teak pole found near the Boundary line of Veerapur and Kodagikere Village by Guard Keroji of Channagiri Range has been seized and kept in the custody of Basappa of Kurubarahalli. Persons having right to the same are requested to submit their claim in a statement to the District Forest Officer, Bhadravati Division within one month from the date of publication of the notice, failing which the teak trough and the pole will lapse to Government under section 42 of the said Regulation.

	Length.	Girth.
Teakwood trough ..	..	9′—9″ x 5—7
Teak pole ...	...	... 15—3 x 1—11

Notification dated 8th January 1932.

Notice is hereby given under section 40 of the Mysore Forest Regulation that one teak pole measuring 16 ft. 6 inches long and 1′—11″ girth lying in the land of Madenahalli Gowda Gangappa and found unclaimed has been seized by the Range Officer, Bhadrapura and is kept in the custody of Mr. Siddappa, Patel of Hanchina Siddapura, Shimoga Taluk. Persons having any right to the teak piece are requested to submit a statement of their claim to the District Forest Officer, Bhadravati, within one month from the date of publication of this notice, failing which the teak piece will lapse to Government under section 42 of the said Regulation.

H. V. RANGASWAMIENGAR,
District Forest Officer.

MYSORE DISTRICT.

Abstract Notification dated 11th December 1931.

The attention of the public is invited to the detailed Notification of date, *re* the sale of timber in the several Depots of the Mysore District, published in pages 1 and 2, Part VI of the *Mysore Gazette*, dated 7th January 1932.

M. A. MUTHANNA,
District Forest Officer.

ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Notice.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 30th January 1932, for restoring Bandehalli Mavinkere Minor tank Reg. No. 615 of Hosakote Taluk. An approximate estimate of quantities is given below These quantities are not guaranteed. The work should be completed by the end of June 1933.

2. The plans detailed estimates and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5. P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 (one hundred and fifty) in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for restoring Bandehally Mavinkere tank of Hosakote Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Excutive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claim for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Chief Engineer will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of works and lump-sum provisions are subject to modifications as per data worked out during execution. For individual items of work under lumpsum provisions the rates tendered for similar items of works will be paid and for other items, the rates as per schedule of rates will be paid at the discretion of the Executive Engineer.

13. Rates for masonry include bond stones to the required percentage at the required intervals of the quality and size to be specified.

Abstract of quantities.

No.	Item of work.	Per	Quantity	Rate
	BUND R. L. 55·40.			Rs. a. p.
1	Clearing lantana jungle and roots entirely grubbed up and ant hills.	Grade	14	
2	Cutting grips and trenches on top and slopes ...	,,	14	
3	Earthwork to raising bund including watering and tamping.	C. yd.	8,424	
4	New stone revetment with jelly backing and wedging	,,	792	
5	Puddle wall	,,	43	
6	Dismantling the top course and resetting old stone with required new jelly backing and wedging.	,,	130	
7	Turfing	Sq. yd.	4,432	
8	Silt clearing from borrow pit gap and using the same to fill the hall[illegible] rear toe of bund.	C.yd.	69	
9	Providing new grade stone with bed slabs including, cutting, figuring and painting.	Each	14	
10	Do Index stones do ...	,,	14	
11	Do B. M. stones do ...	,,	2	
12	Do Guage stone do ...	,,	1	
13	Do Register No. and date stone ...	,,	1	
	WASTE WEIR AT R. L. 51·00.			
1	Benching the [illegible]r surface (3") ...	Sq.ft.	231	
2	Cement washing	L. S.	...	
3	Masonry burnt stone in surki mortar ...	C.ft.	593	
4	Burnt stone slabs 6" thick dressed	Sq.ft.	148	
5	Deep cement pointing	Sqr.	6·42	
6	Approach clearing to be racked out by burning up to R. L. 51·00 and used to revetment.	L. S.	...	
7	Cutting joggle joints	Each	20	

N. G. KRISHNA IYENGAR,
Executive Engineer.

6 B